



City of Dallas
APPROVED
 Building Inspection
 07/14/23

City of Dallas
REVIEW COMPLETE
 Engineering Paving/Drainage
 09/29/22

811
 Know what's below.
 Call before you dig.

PROPOSED LEGEND

PROPERTY LINE/RIGHT OF WAY LINE	CONCRETE CURB AND GUTTER. SEE DETAIL 01C.	LIMITS OF HEAVY DUTY CONCRETE PRIVATE PAVING. REFER TO 008-50.
PROPOSED PARKING SPACES	GRATE INLET	CONCRETE SIDEWALK 4" THICK, 3,000 PSI CONCRETE WITH #3 BARS @ 24" C.C. #3 DOWELS @ 18" ON 12" LIME STABILIZED SUBGRADE. REFER TO 008-50.
GRATE INLET	DRIVE APPROACH	DRIVE APPROACH MINIMUM 8" THICK, 4,500 PSI CONCRETE WITH #3 BARS @ 24" C.C. #4 DOWELS @ 12" ON 12" LIME STABILIZED SUBGRADE. REFER TO NOTES FOR OPTIONS.
SITE DETAILS	TURN LANE	TURN LANE MINIMUM 11" THICK, 4,500 PSI CONCRETE WITH #3 BARS @ 24" C.C. #3 DOWELS @ 12" C.C. ON 12" LIME STABILIZED SUBGRADE. REFER TO CITY OF DALLAS STANDARDS.
OSA GUARD POST	FIRE LANE LOCATION	FIRE LANE LOCATION PER CITY OF DALLAS STANDARDS.

- PROPOSED TURNING LANE NOTES:**
- MINIMUM TRANSITION LENGTH IS 109.9'. MINIMUM STORAGE IS 90'. MINIMUM CURVE RADIUS #1 IS 400'. MINIMUM CURB RADIUS #2 IS 200'.
 - MINIMUM PAVEMENT DEPTH IS 11". TURN LANE PAVEMENT DEPTH SHOULD MATCH EXISTING STREET PAVEMENT DEPTH IF EXISTING PAVEMENT DEPTH IS THICKER THAN THE MINIMUM THICKNESS FOR THE TURN LANE.
 - HAND FINISH CLASS - TEST STRENGTH IS 4,500 PSI COMPRESSIVE STRENGTH AT 28 DAYS AFTER PLACEMENT. #4 BARS ARE REQUIRED FOR CONCRETE THICKNESS THAT IS 9" OR GREATER, SPACED ON 24" CENTERS.
 - SUBGRADE PREPARATION SHALL BE LIME TREATED SUBGRADE. IN LIEU OF THIS REQUIREMENT, TWO ADDITIONAL INCHES OF CONCRETE MUST BE ADDED TO THE CONCRETE THICKNESS.
 - STANDARD SUBGRADE COMPACTION UNDER STREET PAVEMENT IS 98% STANDARD PROCTOR DENSITY AT MINUS 2% TO PLUS 4% OF OPTIMUM MOISTURE TO THE DEPTH SPECIFIED.
 - 1" REDWOOD EXPANSION JOINTS ARE REQUIRED AT ALL ABRUPT CHANGES IN ALIGNMENT WIDTH, OR EVERY 150 FEET, BEGINNING AT THE CURB RETURN.
 - AT ALL EXPANSION JOINTS, 24" LONG, #8 (1") SMOOTH DOWEL IS REQUIRED EVERY 12" ON CENTER AND MUST BE GREASED AND CAPPED.
 - SAWED TRANSVERSE DUMMY JOINTS SHALL BE SPACED EVERY 15 FEET.
- DRIVE APPROACH NOTES:**
- MINIMUM PAVEMENT DEPTH IS 8". DRIVE APPROACH PAVEMENT DEPTH SHOULD MATCH ON-SITE PAVEMENT DEPTH IF ON-SITE PAVEMENT IS THICKER THAN THE MINIMUM THICKNESS FOR APPROACHES.
 - HAND FINISH CLASS - TEST STRENGTH IS 4,500 PSI COMPRESSIVE STRENGTH AT 28 DAYS AFTER PLACEMENT.
 - STANDARD SUBGRADE COMPACTION UNDER DRIVE APPROACHES IS 98% STANDARD PROCTOR DENSITY AT MINUS 2% TO PLUS 4% OF OPTIMUM MOISTURE TO THE DEPTH SPECIFIED.
 - #3 BARS ARE REQUIRED FOR CONCRETE THICKNESS LESS THAN 9". SPACED ON 24" CENTERS. #4 BARS ARE REQUIRED FOR CONCRETE THICKNESS THAT IS 9" OR GREATER, SPACED ON 24" CENTERS.
 - 1" REDWOOD EXPANSION JOINTS ARE REQUIRED AT ALL PROPERTY LINES.
 - DOWEL PROPOSED DRIVE APPROACH INTO EXISTING PAVEMENT WITH 24" LONG, #4 BARS, AT 12" ON CENTER, EPOXYED IN.
 - FOR THE EXPANSION JOINT AT THE PROPERTY LINE, 24" LONG, #8 (1") SMOOTH DOWEL IS REQUIRED FOR PAVING THICKNESS GREATER THAN 9". ALL DOWELS REQUIRED EVERY 12" ON CENTER AND MUST BE GREASED AND CAPPED.
 - DRIVE APPROACHES REQUIRE A SAW JOINT AT THE CENTERLINE.
 - IN LIEU OF ALL OPTIONS EXCEPT FOR COMPACTED SUBGRADE, TWO ADDITIONAL INCHES OF CONCRETE MUST BE ADDED TO THE CONCRETE THICKNESS.

SITE DATA

SITE AREA	20.42 AC (889,337 SF)
TOTAL ONSITE PAVING	15.95 AC (694,634 SF)
EXISTING TRAILER PARKING	71 SPACES
PROPOSED TRAILER PARKING	217 SPACES
TOTAL TRAILER PARKING	288 SPACES
EXISTING TRUCK PARKING	37 SPACES
PROPOSED TRUCK PARKING	50 SPACES
TOTAL TRUCK PARKING	87 SPACES

NOTE: SUBGRADE PREPARATION THROUGHOUT THE SITE SHALL BE LIME TREATED SUBGRADE.

NOTE FOR PRIVATE PAVING WITHIN PROPERTY ONLY: PRIMARY BID SCENARIO AS ASPHALT PAVEMENT (DETAIL 08B) WITH CONCRETE LANDING STRIPS (DETAIL 08D) ALTERNATE BID SCENARIO AS FULL CONCRETE PAVEMENT (DETAIL 08C).

NOTE: ANY TRAFFIC CONTROL PLAN (TCP) MUST BE SUBMITTED TO THE DEPARTMENT OF PUBLIC WORKS FOR REVIEW AND APPROVAL BY TRAFFIC SAFETY COORDINATORS PRIOR TO START OF CONSTRUCTION. NO TRAFFIC LANE OR SIDEWALK ALONG ANY PUBLIC STREET OR ALLEY IS TO BE CLOSED WITHOUT FIRST OBTAINING THE APPROPRIATE PERMIT(S). CLOSURE OF ANY TRAFFIC LANE MUST BE RESTRICTED TO THE HOURS OF 9:30 A.M. TO 3:30 P.M. WORKDAYS (HOURS MAY DIFFER IN SCHOOL ZONES). CONTRACTOR MUST CALL (214) 948-4250 TO REQUEST APPROVAL OF TCP AND TO OBTAIN A RIGHT-OF-WAY PERMIT.

NOTE: ALL CURB AND GUTTER IN THE PUBLIC ROW SHALL BE BUILT PER DETAIL 01A TO CITY OF DALLAS AND TXDOT STANDARDS.

SPECIAL NOTE: ALL PROPOSED WALKS AND RAMPS ARE DESIGNED TO ADA AND TAS STANDARDS. EXISTING WALKS AND ACCESSIBLE RAMPS TO REMAIN IN PLACE ARE DETERMINED TO MEET ADA AND TAS STANDARDS PER ASSESSMENT OF THE DETAILED SURVEY INFORMATION.

- SITE NOTES**
- 12G 4 INCH WIDE PAINTED WHITE STRIPES, 2 FOOT O.C. @ 45 DEGREES (PER TRAFFIC COMMENTS).
 - 13B LIMITS OF HEAVY DUTY CONCRETE PAVING.
 - 18E POINT OF RELOCATION.
 - 20B REPLACE/RESTORE SIDEWALK PER LOCAL CODES TO MATCH EXISTING, 810 LF OF TOTAL WALK REPLACEMENT.
 - 20D REPLACE/RESTORE SIDEWALK TO MATCH EXISTING.
 - 21A TAPER CURB TO MATCH EXISTING CURB.
 - 21B TAPER CURB FROM 6 INCHES TO 0 INCHES OVER 2 FEET.
 - 70A GUARD SHACK PER OWNER SPECIFICATIONS.
 - 70B BULLYDOG ELECTRIC FENCE PER OWNER SPECIFICATIONS.
 - 70D PROTECTED AREA FOR UTILITIES.

- SITE DETAILS**
- 01A TYPE A CONCRETE CURB AND GUTTER
 - 01C TYPE C CONCRETE RAISED CURB AND GUTTER
 - 01H TYPE H CURB (ROLL OVER)
 - 02A PRECAST CONCRETE WHEEL STOP
 - 02E BOLLARD
 - 07A SECURITY FENCE
 - 08A STANDARD DUTY ASPHALT PAVING
 - 08B HEAVY DUTY ASPHALT PAVING
 - 08C HEAVY DUTY CONCRETE PAVING
 - 08D UNREINFORCED STANDARD DUTY CONCRETE
 - 70C INTERIOR CURB SECTION

- GENERAL SITE NOTES**
- ALL DIMENSIONS SHOWN ARE TO THE FACE OF CURB UNLESS OTHERWISE NOTED.
 - ALL CURB RETURN RADII SHALL BE 3', AS SHOWN TYPICAL ON THIS PLAN, UNLESS OTHERWISE NOTED.
 - PRIVATE PAVING, UNLESS OTHERWISE SHOWN, CALLED OUT OR SPECIFIED HEREON OR WITHIN THE SPECIFICATIONS. ALL CURB AND GUTTER ADJACENT TO ASPHALT PAVING SHALL BE INSTALLED PER DETAIL 01C. ALL CURBING ADJACENT TO CONCRETE PAVING SHALL BE INSTALLED PER DETAIL 01C. ASPHALT PAVEMENT SHALL BE INSTALLED IN ACCORDANCE WITH DETAIL 08B OVER THE ENTIRE PARKING LOT AREA AND 08C OVER ALL APPROACH DRIVES.
 - PAVING IN PUBLIC RIGHT OF WAY TO BE INSTALLED PER DALLAS STANDARDS 251D-1 SHEETS 1001, 1002, 1003 AND 1004 AND DALLAS STREET DESIGN MANUAL.
 - ALL CONTROL GATES MUST BE SET BACK A MINIMUM OF 20' FROM THE BACK OF STREET CURB PER DALLAS CITY CODE, SEC. 51A-4.602 (A)(2)(B).
 - PROPOSED PAVING WILL REQUIRE PAVEMENT MARKINGS IN BOTH PUBLIC AND STATE RIGHT OF WAY.
 - ALL WALKS MUST BE COMPLETE ALONG THOROUGHFARE PRIOR TO ACCEPTANCE OF ANY IMPROVEMENTS.



CONTRACT INFORMATION

CONTRACT NO. DP20-028	DATE 02/03/2022
CONTRACTOR All State Paving, INC.	
CONTRACT NO.	DATE
CONTRACTOR	
CONTRACT NO.	DATE
CONTRACTOR	

REVISIONS

REV NO.	DATE	DESCRIPTION	BY

CEI ENGINEERING ASSOCIATES, INC.
 3030 LBJ FREEWAY, SUITE 100
 DALLAS, TX 75234
 PHONE: (972) 488-3737
 FAX: (972) 488-6732

STATE OF TEXAS REGISTRATION NUMBER F-7524

PLAT NO. S212-236	BUILDING PERMIT NO. 2002031054	DEV ENGINEERING TRACKING NOS. DP20-028
-------------------	--------------------------------	--

OVERALL SITE PLAN

JB HUNT MAINTENANCE FACILITY
3140 DUNCANVILLE ROAD
 DEVELOPMENT SERVICES
 CITY OF DALLAS, DALLAS COUNTY, TEXAS

REVIEW BY:	DRAWN BY:	DATE	FILE	NUMBER	SHEET
DAM	CO	7/20/2022	411Q	32516	C2.0