

Exhibit C

**15' SANITARY SEWER EASEMENT ABANDONMENT
EVERGLADE PARK ADDITION
CITY BLOCK 6127
DAVID A. BADGLEY SURVEY, ABSTRACT NO. 65
CITY OF DALLAS, DALLAS COUNTY, TEXAS**

BEING a 9,051 square feet (0.2078 acres) tract of land situated in the David A. Badgley Survey, Abstract No. 65, and being part of that certain called 8.18 acre tract of land as described in warranty deed to the City of Dallas, a Texas municipal corporation, recorded in Volume 68081, Page 1203, Deed Records, Dallas County, Texas (D.R.D.C.T.), same being Everglade Park, an addition to the City of Dallas in City Block 6127, according to the plat thereof as recorded in Volume 75072, Page 618, D.R.D.C.T., same being a portion of a 15' sanitary sewer easement shown of said Everglade Park plat and recorded in Volume 75072, Page 618, D.R.D.C.T., and being more particularly described by metes and bounds as follows:

COMMENCING at a City of Dallas brass monument found (record monument) at the intersection of Jim Miller Road (120' right-of-way) and Showbend Lane (50' right-of-way), same being the northwest corner of that certain called 6.887 acre tract of land as described in warranty deed to the City of Dallas, recorded in Volume 4893, Page 220, D.R.D.C.T.;

THENCE South 00°09'52" West, with the west line of said 6.887 acre City of Dallas tract and the east right-of-way line of said Jim Miller Road, a distance of 500.00 feet to a City of Dallas brass monument found (record monument, Grid Northing=6,974,039.52, Easting=2,521,635.17) for the southwest corner of said 6.887 acre City of Dallas tract, same being the northwest corner of said Everglade Park, same being the **POINT OF BEGINNING** of the herein described tract;

THENCE South 89°50'08" East, departing the east right of way line of said Jim Miller Road and the west line of said Everglade Park, with the north line of said Everglade Park and the south line of said 6.887 acre City of Dallas tract, a distance of 575.00 feet to a City of Dallas brass monument found (record monument, Grid Northing=6,974,037.87, Easting=2,522,210.08) for the northeast corner of said Everglade Park and the southeast corner of said 6.887 acre City of Dallas tract;

THENCE South 24°51'09" East, with the east line of said Everglade Park, a distance of 16.55 feet to the southeast corner of the herein described tract;

THENCE North 89°50'08" West, departing the east line of said Everglade Park, with the south line of said 15' sanitary sewer easement, a distance of 567.00 feet to a point for corner;

THENCE South 00°09'52" West, with the east line of said 15' sanitary sewer easement, a distance of 25.00 feet to a point for corner;

THENCE North 89°50'08" West, crossing said 15' sanitary sewer easement, a distance of 15.00 feet to a point for corner in the east right-of-way line of said Jim Miller Road;

THENCE North 00°09'52" East, with the east right-of-way line of said Jim Miller Road, a distance of 40.00 feet to the **POINT OF BEGINNING**, containing 9,051 square feet (0.2078 acres) of land, more or less.

For SPRG use only	
Reviewed By:	_____
Date:	_____
SPRG No:	_____

Exhibit C

15' SANITARY SEWER EASEMENT ABANDONMENT
EVERGLADE PARK ADDITION
CITY BLOCK 6127
DAVID A. BADGLEY SURVEY, ABSTRACT NO. 65
CITY OF DALLAS, DALLAS COUNTY, TEXAS


BASIS OF BEARINGS: TEXAS COORDINATE SYSTEM OF 1983, NORTH CENTRAL ZONE 4202,
NORTH AMERICAN DATUM OF 1983. ADJUSTMENT REALIZATION OF 2011.

* SURVEYOR'S CERTIFICATE *

TO ALL PARTIES INTERESTED IN TITLE TO THE PREMISES SURVEYED, I DO HEREBY CERTIFY THAT THE ABOVE LEGAL DESCRIPTION WAS PREPARED FROM PUBLIC RECORDS AND FROM AN ACTUAL AND ACCURATE SURVEY UPON THE GROUND AND THAT SAME IS TRUE AND CORRECT.

An exhibit of even date accompanies this metes-and-bounds description.

JQ Infrastructure, LLC



Sean I. Compton, RPLS
Registered Professional Land Surveyor
Texas No. 6766


Date: *2022-03-04*



For SPRG use only	
Reviewed By:	_____
Date:	_____
SPRG No:	_____

SHOWBEND LANE Exhibit C

(50' WIDTH RIGHT-OF-WAY)



JIM MILLER ROAD
(120' WIDTH RIGHT-OF-WAY)
(VOL. 71143, PG. 1147 D.R.D.C.T.)

15' SANITARY SEWER EASEMENT ABANDONMENT

PORTION OF CITY OF DALLAS BLOCK 6127
DAVID A. BADGLEY SURVEY, ABSTRACT No. 65
EVERGLADE PARK ADDITION VOLUME 75072, PAGE 618 D.R.D.C.T.
CITY OF DALLAS, DALLAS COUNTY, TEXAS

EVERGLADE ROAD
(60' WIDTH RIGHT-OF-WAY)

(IN FEET)
1 inch = 100 ft.

LEGEND	
<input checked="" type="checkbox"/>	MONUMENT FOUND (AS NOTED)
<input type="checkbox"/>	POINT FOR CORNER
	EASEMENT LINE
	PROPERTY LINE (AS NOTED)
	RIGHT-OF-WAY LINE (AS NOTED)
D.R.D.C.T.	DEED RECORDS DALLAS COUNTY TEXAS
R.M.	RECORD MONUMENT
SQ. FT.	SQUARE FEET
P.O.C./P.O.B.	POINT OF COMMENCING/BEGINNING



(For SPRG use only)

Reviewed by: _____
Date: _____
SPRG No.: _____

shaping the built environment

JQ INFRASTRUCTURE
100 GLASS STREET, SUITE 201
P| 214.752.9098
JQI JOB NO: 4170307

DALLAS, TEXAS 75207
JQENG.COM
TEXAS REGISTERED SURVEYING FIRM 10193718

NOTE:
ALL BEARINGS ARE REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983, NORTH CENTRAL ZONE (4202), NORTH AMERICAN DATUM 1983. THE SURFACE SCALE FACTOR FOR THIS PROJECT IS 1.000136506. DISTANCES, AND AREAS SHOWN ARE SURFACE. COORDINATES SHOWN ARE GRID. SUBJECT TO RIGHTS OF EXISTING EASEMENTS. METES AND BOUNDS DESCRIPTION OF EVEN DATE ACCOMPANY THIS MAP OF SURVEY.

Name: SEAN I. COMPTON
Registered Professional Land Surveyor
Texas No. 6766
Date of Survey: 2022-03-04

DRAWN:	SIC
CHECKED:	SIC
DATE:	2022-03-02
CREW:	MS/TD