

CITY PLAN COMMISSION

THURSDAY, MARCH 23, 2023

FILE NUMBER: S223-097

CHIEF PLANNER: Mohammad H. Bordbar

LOCATION: Arboreal Drive at West Northwest Highway / State Highway Loop 12, northeast corner.

DATE FILED: February 24, 2023

ZONING: R-7.5(A)

CITY COUNCIL DISTRICT: 9 **SIZE OF REQUEST:** 1.175-acres

MAPSCO: 37A

APPLICANT/OWNER: White Rock Fellowship

REQUEST: An application to create one 1.175-acre lot from a tract of land in City Block 5439 on property located on Arboreal Drive at West Northwest Highway / State Highway Loop 12, northeast corner.

SUBDIVISION HISTORY:

1. S223-096 is a request northwest of the present request to create one 1.390-acre lot from a tract of land in City Block 5438 on property located on Town North Drive at West Northwest Highway / State Highway Loop 12, northeast corner. The request is scheduled for public hearing on March 23, 2023.

STAFF RECOMMENDATION: Section 51A-8.503 states that “lots must conform in width, depth, and area to the pattern already established in the adjacent areas, having due regard to the character of the area, its particular suitability for development, and taking into consideration the natural topography of the ground, drainage, wastewater facilities, and the proposed layout of the streets.”

It is a policy of the city that institutional uses generally require greater land area than traditional residential or non-residential lots and generally serve, and are compatible with the neighborhood; therefore, staff concludes that the request is in compliance with Section 51A-8.503 and with the requirements of R-7.5(A) Single Family District; therefore, staff recommends approval of the request subject to compliance with the following conditions:

General Conditions:

1. The final plat must conform to all requirements of the Dallas Development Code, Texas Local Government Code, Texas Land Surveying Practices Act and the General Rules and Regulations of the Texas Board of Land Surveying.
2. Department of Development Services, Engineering Division must verify that the plat conforms with the water, wastewater, and easement requirements under the provisions of Chapter 49 of the Dallas City Code.
3. Compliance with all plans, contracts, ordinances, and requirements of the City of Dallas. *Section 51A-8.102(a), (b), (c), and (d)*
4. The number and location of fire hydrants must comply with the Dallas Fire Code.
5. Any new or existing structure may not extend across new property lines. *Section 51A-8.503(e)*

6. On the final plat, all easement abandonments, and ROW abandonments must be by separate instrument with the recording information shown on the face of the plat. A release from the Real Estate Division is required prior to the plat being submitted to the Chairman for signature.
7. On the final plat, include two boundary corners tagged with these coordinates: "Texas State Plane Coordinate System, North Central Zone, North American Datum of 1983 on Grid Coordinate values, No Scale and no Projection."
8. On the final plat, monument all set corners per the Monumentation Ordinance. Prior to submittal of the final plat for the Chairman's signature. The monuments must be verified by the Chief City Surveyors Office in the Public Works Department. *Section 51A-8.617*
9. Provide ALL supporting documentation (i.e., deeds, plats, ordinances, easements...etc.) with a completed Final Plat Checklist to the Survey Plat Review Group (**SPRG**) with the Final Plat Submittal **after** City Plan Commission Approval.
10. Prior to the final plat, submit a tree survey to the Arborist. A release from the arborist is required prior to an early release request or the recordation of the plat, whichever occurs first.
11. The number of lots permitted by this plat is one.

Paving & Drainage Conditions:

12. Submit a full set of Civil Engineering Plans (drainage, paving, street signage/markings/lighting) prepared per City Standards by a licensed (TX) Professional Engineer to Engineering Division in Room 200, Oak Cliff Municipal Center (i.e., 311T/DP). Additions and alterations to the public infrastructure require approval and may require private development contracts with bonds. 51A-8.102 (c); 8.601(b)(4),(5),(6),(7),(8),(9)
13. Detention may be required if the capacity of available outfall is not adequate to carry the developed runoff. Section 51A-8.611(c).
14. Place a note on the final plat stating "Lot-to-Lot drainage will not be allowed without proper City of Dallas Engineering Division approval" 51A 8.611(e)

Right-of way Requirements Conditions:

15. On the final plat, dedicate 7.5 feet of right-of-way (via fee simple) from the established center line of the Alley. *Section 51A 8.602(c)*
16. On the final plat, dedicate 28 feet of right-of-way (via fee simple or street easement) from the established centerline of Arboreal Drive. Sections 51A-8.602(c), 51A-8.604(c) and 51A-8.611(c).
17. On the final plat, dedicate a minimum 10-foot by 10-foot corner clip (via fee simple or street easement) at the intersection of Northwest Highway / State Highway Loop 12 and Arboreal Drive. Section 51A 8.602(d)(1)

18. Prior to final plat, a larger corner clip may be requested during engineering plan and traffic review to accommodate an adequate turning radius, or to maintain public/traffic appurtenances, within the area of the corner clip. Section 51A 8.602(d)(1), 51A 8.608(a)
19. On the final plat, dedicate a 15-foot by 15-foot Alley Sight Easement at the intersection of Northwest Highway / State Highway Loop 12 & the alley. *Section 51A-8.602(e)*
20. On the final plat, add the note: "TxDOT approval may be required for any driveway modification or new access point(s)." No citation.

Survey (SPRG) Conditions:


21. Prior to final plat, submit a completed final plat checklist and all supporting documents.
22. On the final plat, show recording information on all existing easements within 150 feet of the property.
23. On the final plat, show all additions or tracts of land within 150 feet of the property with recording information. Platting Guidelines.


Dallas Water Utilities Conditions:

24. Engineer must furnish plans for water and sanitary sewer. Developer must furnish a contract for water and sanitary sewer. Sections 49-60(g)(1) and (2) and 49-62(b), (c), and (f).
25. Additional design information is required for assessment. Site plan must be submitted showing proposed development, building finished floor elevation, development, existing mains – including downstream manhole, and proposed water and wastewater service locations. Submit water/wastewater engineering plans to 320 E. Jefferson Blvd., Room 200, Attention: Water and Wastewater Engineering.
26. Wastewater main improvements are required by Private Development Contract. Submit water/wastewater engineering plans to 320 E. Jefferson Blvd., Room 200, Attention: Water and Wastewater Engineering.


Real Estate / Arborist / Street Name / GIS, Lot & Block Conditions:

27. On the final plat, change "Northwest Highway (State Highway Loop 12)" to "Northwest Highway / State Highway Loop 12". Section 51A-8.403(a)(1)(A)(xii)
28. On the final plat, identify the property as Lot 1 in City Block A/5439. Ordinance 1A, Page 131 pages 131-148, Section 2 (passed August 13, 1872).





 1:2,400	<h2 style="text-align: center;">AERIAL MAP</h2> <p><input type="checkbox"/> Area of Request <input type="checkbox"/> Recent History</p>	Case no: <u>S223-097</u> Date: <u>3/6/2023</u>
--	---	---



PRELIMINARY PLAT
TOWN NORTH FELLOWSHIP NO. 2
LOT 1, BLOCK A/5439
 SHEET 1 OF 2
 1:50 ASSESSOR'S SCALE
 D. A. METROCK SURVEY, ABSTRACT NO. 997
 CITY OF DALLAS, DALLAS COUNTY, TEXAS
 ENGINEERING NUMBER D923-XXX
Gonzalez & Schneider State 500 Main Street, Suite 200
 2100 Lamar Boulevard, Suite 200
 DALLAS, TEXAS 75201
 Telephone: 972-311-4655
 Fax: 972-311-4655
 7/27/2023 11:48 AM

NOTES
 1. Survey system for this plat is based on the standard geodetic datum of North American Datum 83. All bearings and distances are given in feet and inches, rounded to the nearest 1/16 of an inch. All bearings are given in degrees, minutes and seconds, rounded to the nearest second. All distances are given in feet and inches, rounded to the nearest 1/16 of an inch.
 2. Lot 1 is to be divided into two lots, each of which shall be subject to the same restrictions as set forth in the plat.
 3. The purpose of this plat is to create one lot from a single tract.
 4. Certain lines, when produced, shall be considered as true lines, and no projection.
 5. No buildings exist on this site.

OWNERS CERTIFICATE

OWNERS DECLARATION

STATE OF TEXAS
COUNTY OF DALLAS
WHEREAS, when this Township was first surveyed in the City of Dallas, Texas, the boundaries of the Township were established by the City of Dallas, Texas, and the boundaries of the Township were established by the City of Dallas, Texas, and the boundaries of the Township were established by the City of Dallas, Texas...

AND WHEREAS, KNOW ALL MEN BY THESE PRESENTS, that I, the undersigned authority, do hereby certify that the above described property as shown on the plat is the same as that shown on the plat, and that the boundaries of the property are as shown on the plat, and that the boundaries of the property are as shown on the plat, and that the boundaries of the property are as shown on the plat...

RELEASED UNDER THE PROVISIONS OF THE PUBLIC INFORMATION ACT, THIS DOCUMENT SHALL NOT BE RECORDED FOR ANY PURPOSE OTHER THAN TO FURNISH INFORMATION TO THE PUBLIC. THE CITY OF DALLAS DOES NOT WARRANT THE ACCURACY OF THIS INFORMATION.

STATE OF TEXAS
COUNTY OF DALLAS
WHEREAS, I, the undersigned authority, do hereby certify that the above described property as shown on the plat is the same as that shown on the plat, and that the boundaries of the property are as shown on the plat, and that the boundaries of the property are as shown on the plat...

PRELIMINARY PLAT
TOWN NORTH FELLOWSHIP NO. 2
LOT 1, BLOCK A/5439
1175 ACBE TRACT
CITY OF DALLAS, TEXAS
CONRAD & SCHNEIDER
ENGINEERING NUMBER DP23-XXX