# CITY PLAN COMMISSION

THURSDAY, MARCH 2, 2023

FILE NUMBER: S223-070

CHIEF PLANNER: Mohammad H. Bordbar

LOCATION: Alexis Drive, east of Preston Road/State Highway 289

#### DATE FILED: February 3, 2023

**ZONING:** MF2-(A)

CITY COUNCIL DISTRICT: 11 SIZE OF REQUEST: 45.139-acres MAPSCO: 15F-15G

# **APPLICANT/OWNER:** Tonti Properties

**REQUEST:** An application to create five lots ranging in size from 5.439-acres to 18.182acres from a 45.139-acre tract of land in City Block A/8178 on property located on Alexis Drive, east of Preston Road/State Highway 289.

**SUBDIVISION HISTORY:** There has been no recent platting activity within close proximity to this request.

**STAFF RECOMMENDATION:** Section 51A-8.503 states that "lots must conform in width, depth, and area to the pattern already established in the adjacent areas, having due regard to the character of the area, its particular suitability for development, and taking into consideration the natural topography of the ground, drainage, wastewater facilities, and the proposed layout of the streets."

• The properties in the immediate area of the request have no established lot pattern with lot areas ranging in size from 15,923 square feet to 309,039 square feet, the properties to north are zoned CR Community Retail District, to the east and southeast are zoned R-16(A) Single Family District and PD 474. (*Please refer to the existing area analysis and aerial map*)

Staff concludes that there is not an established lot pattern in the immediate area of the request and the request complies with the requirements of Section 51A-8.503 and the MF-2(A) Multi Family District; therefore, staff recommends approval of the request subject to compliance with the following conditions:

## General Conditions:

- 1. The final plat must conform to all requirements of the Dallas Development Code, Texas Local Government Code, Texas Land Surveying Practices Act and the General Rules and Regulations of the Texas Board of Land Surveying.
- 2. Department of Development Services, Engineering Division must verify that the plat conforms with the water, wastewater, and easement requirements under the provisions of Chapter 49 of the Dallas City Code.
- 3. Compliance with all plans, contracts, ordinances, and requirements of the City of Dallas. Section 51A-8.102(a), (b), (c), and (d)
- 4. The number and location of fire hydrants must comply with the Dallas Fire Code.

- 5. Any new or existing structure may not extend across new property lines. *Section* 51A-8.503(e)
- 6. On the final plat, all easement abandonments, and ROW abandonments must be by separate instrument with the recording information shown on the face of the plat. A release from the Real Estate Division is required prior to the plat being submitted to the Chairman for signature.
- 7. On the final plat, include two boundary corners tagged with these coordinates: "Texas State Plane Coordinate System, North Central Zone, North American Datum of 1983 on Grid Coordinate values, No Scale and no Projection."
- 8. On the final plat, monument all set corners per the Monumentation Ordinance. Prior to submittal of the final plat for the Chairman's signature. The monuments must be verified by the Chief City Surveyors Office in the Public Works Department. *Section 51A-8.617*
- Provide ALL supporting documentation (i.e., deeds, plats, ordinances, easements...etc.) with a completed Final Plat Checklist to the Survey Plat Review Group (SPRG) with the Final Plat Submittal <u>after</u> City Plan Commission Approval.
- 10. Prior to the final plat, submit a tree survey to the Arborist. A release from the arborist is required prior to an early release request or the recordation of the plat, whichever occurs first.
- 11. The number of lots permitted by this plat is five.

# Paving & Drainage Conditions:

- 12. Submit a full set of Civil Engineering Plans (drainage, paving, street signage/marking/lighting) prepared per City Standards by a licensed (TX) Professional Engineer to Engineering Division in Room 200, Oak Cliff Municipal Center (i.e., 311T/DP). Additions and alterations to the public infrastructure require approval and may require private development contracts with bonds.51A-8.102 (c); 8.601(b)(4),(5),(6),(7),(8),(9)
- 13. Detention may be required if the capacity of available outfall is not adequate to carry the developed runoff. Section 51A-8.611(c).
- 14. Place a note on the final plat stating "Lot-to-Lot drainage will not be allowed without proper City of Dallas Engineering Division approval" 51A 8.611(e)

## **Right-of way Requirements Conditions:**

- 15. On the final plat, add the note: "TxDOT approval may be required for any driveway modification or new access point(s)." No citation.
- 16. Existing drainage conveyance within the property is required to be sized in compliance with Section 51A-8.611(a)(1) of the City of Dallas Code.
- 17. Must coordinate with Transportation Department for any traffic signal requirements that are deemed necessary for improving pedestrian accessibility

and safety related to site development (Contact Srinivasa Veeramallu with Traffic Signals). *51A-8.606, 51A-8.608* 

#### Flood Plain Conditions:

- 18. On the final plat, determine the 100-year water surface elevation across this addition.
- 19. On the final plat, dedicate floodway easement, floodway management area or floodway easement (within common area), with the appropriate easement statement included on the face of the Plat. <u>51A 8.611(d); DWU Floodplain</u> <u>Management; Drainage Design Manual Addendum V</u>
- 20. On the final plat, include additional paragraph in Owner's Certificate (pertaining to the floodplain). <u>51A 8.611(d); DWU Floodplain Management; Drainage Design</u> <u>Manual Addendum V</u>
- 21. On the final plat, specify minimum fill and minimum finished floor elevations. *Section 51A-8.611(d), Trinity Watershed Management.*
- 22. On the final plat, show the natural channel set back from the crest of the natural channel. Section 51A-8.611(d), Trinity Watershed Management.
- 23. Prior to submission of the final plat, set floodway monument markers and provide documentation that the monuments have been set. Section 51A-8.617(d)(1), (2), (3), and (4)
- 24. Provide information regarding Fill Permit or Floodplain Alteration Permit if such permit is applied for.

## Survey (SPRG) Conditions:

- 25. Prior to final plat, submit a completed final plat checklist and all supporting documents.
- 26. On the final plat, show distances/width across all adjoining right-of-way. Platting Guidelines.
- 27. On the final plat, all access easement(s) must be recorded by separate instrument(s) and the recording information must be shown on the final plat. Platting Guidelines.


#### Dallas Water Utilities Conditions:


- 28. Engineer must furnish plans for water and sanitary sewer. Developer must furnish a contract for water and sanitary sewer. Sections 49-60(g)(1) and (2) and 49-62(b), (c), and (f).
- 29. Additional design information is required for assessment. Site plan must be submitted showing proposed development, building finished floor elevation, development, existing mains including downstream manhole, and proposed water and wastewater service locations. Submit water/wastewater engineering plans to 320 E. Jefferson Blvd., Room 200, Attention: Water and Wastewater Engineering.


- 30. Water and wastewater main improvements are required by Private Development Contract. Submit water/wastewater Engineering Plans to 320 E. Jefferson Blvd., Room 200, Attention: Water and Wastewater Engineering.
- 31. Existing and any proposed Water and Wastewater Easements must be shown and/or increased to conform to current design standards. **Notice:** Minimum DWU easement size 20' for one utility and 25' for both water and sewer. Larger diameter or deeper mains may require additional width.
- 32. Prior to final plat, fire protection improvements may be required.


## Real Estate / Arborist / Street Name / GIS, Lot & Block Conditions:


- On the final plat, change "Preston Road/State Highway 289 Formerly Known As State Highway 14" to "Preston Road (State Highway 289). Section 51A-8.403(a)(1)(A)(xii)
- 34. On the final plat, Bold the "Belt Line Road" label sheet 1.
- 35. Prior to final plat, provide documentation of Belt Line Road and Elmo Hutchins Road for Alexis Drive.
- 36. On the final plat, identify the property as Lots 5-9 in City Block A/8178. Ordinance 1A, Page 131 pages 131-148, Section 2 (passed August 13, 1872).











City Plan Commission Date: 03/02/2023

