



LEGEND

- PROPOSED CONCRETE PAVEMENT
- PROPOSED GREEN NO-TAXI ISLANDS
- PROPOSED YELLOW MARKINGS
- SURVEY CONTROL POINT

ITEMS OF WORK

BID SCHEDULES I, III, AND IV:

- DEMOLISH EXISTING PAVEMENT.
- CONSTRUCT APRON SECTION.
- INSTALL NEW INCANDESCENT AND LED TAXIWAY EDGE LIGHTS.
- INSTALL TAXIWAY EDGE LIGHT REFLECTORS.
- INSTALL NEW PAVEMENT MARKINGS.

BID SCHEDULE II:

- INSTALL NEW LED TAXIWAY EDGE LIGHTS AND REPLACE INCANDESCENT TAXIWAY EDGE LIGHT FIXTURES WITH LED LIGHT FIXTURES.

- NOTES:**
- CONTRACTOR SHALL PROTECT ALL CONTROL POINTS TO REMAIN. ANY DAMAGE TO THESE CONTROL POINTS SHALL BE REPAIRED AT NO COST TO THE OWNER. REPAIRS SHALL BE COORDINATED WITH THE ENGINEER AND SHALL BE COMPLETED BY A LICENSED SURVEYOR. FINAL RESULTS OF THE RE-SET MONUMENT SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL.
 - CONTRACTOR SHALL VERIFY CONTROL POINTS AND NOTIFY ENGINEER OF ANY DISCREPANCIES PRIOR TO BEGINNING CONSTRUCTION.
 - BASIS FOR BEARINGS SHOWN HEREON IS THE TEXAS STATE PLANE COORDINATE SYSTEM, NORTH AMERICAN DATUM OF 1983 (NAD83), TEXAS NORTH CENTRAL ZONE, 4202. SURVEY CONDUCTED BY ARS ENGINEERS.

SURVEY CONTROL POINTS

NORTHING	EASTING	ELEVATION (FT)	DESCRIPTION
6935252.86	2471342.12	653.43	MONARD NO 1
6936054.70	2469072.41	656.30	SACS/RBD E
693129.80	2471124.88	654.80	PACS/RBD ARP
6934631.30	2471207.47	655.10	58CIRST / BLUE ARS
6933840.06	2471754.90	651.85	58CIRST / BLUE ARS